

SURVEY & REMONUMENTATION

APR 25 1995

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:30

COMMISSION

For corners in

Ottawa

(County)

Located in:
Jamestown Township

Corner Code #

Public Land Survey

T 5N R 13W

K-7

T _____ R _____

T _____ R _____

T _____ R _____

Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

Miscellaneous

S _____ T _____ R _____

Property in Sec.

S _____ T _____ R _____

Phyllis Redburn
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
2. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Rodney D. Unema, in a field survey on Nov. 7, 19 94,
to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

1. Description of original monument and accessories and/or subsequent restoration:

K-7 Corner common to Sections 13, 14, 23 and 24

Original gov't cor. set in Dec. 1831
by Sylvester Sibley
Set post
Beech 12" N74°E 24 links
Sugar 24" N67°W 25 links

L.C.R.C. Liber 2, Page 389 (Nov. 1973)
Found Mon. Box
Nail in side T & P Pole SE 58.57'
Nail in side T.Pole SW 67.16'
Nail in side T.Pole NW 42.81'
Nail in side T & P Pole NE 61.45'

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7
Found 3/4" iron bar in Mon. box at C/L "X" of Byron Road and 8th Ave.
Found nail & bottle cap in N'ly side T.Pole S65°W 67.23'
Found nail & bottle cap in SE side P.Pole N50°E 61.44'
Found nail & bottle cap in SW side P.Pole S55°E 58.56'

Accepted as a careful perpetuation of the position of the original corner,
and placed a Std. O.C. Cap on existing 3/4" solid iron rod.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/21/94

3. Description of monument for corner and accessories established to perpetuate location of the corner:

K-7 Corner common to Sections 13, 14, 23 and 24
Std. O.C. cap on 3/4" iron bar in Mon. Box
at C/L "X" of Byron Road and 8th Avenue
Set nail & O.C. tag in NW side of T.Pole
Set nail & O.C. tag in NE side of 24" Maple
Set nail & O.C. tag in SE side of P.Pole
Set nail & O.C. tag in SW side of P.Pole

S65°W 67.23'
N55°W 57.59'
N50°E 61.44'
S55°E 58.56'



Signed by Rodney D. Unema

Date Nov. 17, 1994

Surveyor's Michigan License No. 33987

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983