

SURVEY & REMONUMENTATION

APR 25 1995

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:30

For corners in **COMMISSION**

D. J. Collins
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County)	Located In: Jamestown Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>13W</u>	<u>K-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Rodney D. Unema, in a field survey on Nov. 7, 1994,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law, established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

K-8 1/4 Corner between Sections 23 and 24	Original gov't corner set in Dec. 1831	L.C.R.C. Liber 5, Page 351
by Sylvester Sibley	(Nov. 1973)	(Dec. 6, 1988)
Set H.W.P.	Found "L" iron	Set Cast Iron Mon.
Beech 7" N50°E 7 links	Nail in side 36" Maple E 31.59'	30" Maple E 31.72'
Beech 18" S50°W 11 links	Nail in side T.Pole W 29.78'	PP W 29.85'
	Nail in side T.Pole NNW 79.15'	PP SE 41.75'

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8
Found 4" dia. Cast Iron Mon. in Mon. Box
on C/L of N-S B.T. Road (8th Avenue)
Found PK nail in NE side P.Pole S35°E 41.74'
Found nail & bottle cap in N side 36" Maple N90°E 31.43'

Accepted as a careful perpetuation of the position of the original corner.

PA. 345 OTTAWA COUNTY
PEER APPROVED 11/21/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 1/4 Corner between Sections 23 and 24	West 1.2'
4" dia. Cast Iron Mon. in Mon. Box	N90°E 31.71'
C/L of N-S B.T. Road (8th Avenue)	S35°E 41.74'
Set nail & O.C. tag in N side 36" Maple	N35°W 82.14'
Set nail & O.C. tag in NE side Service Pole	N90°W 51.73'
E'ly corner of 1.6 x 1.6 brick pillar of entry sign	
S'ly corner of 1.6 x 1.6 brick pillar of entry sign	
Fence row to West	
+ Tree row to East	



Signed by Rodney D. Unema
Surveyor's Michigan License No. 33987

Date Nov. 17, 1994