

**SURVEY & REMONUMENTATION**

APR 25 1995

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:30

*Rodney D. Unema*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

Ottawa  
(County)

Located In:

Corner Code #

Jamestown Township

1. Public Land Survey	T	5N	R	13W	K-10
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

1. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
2. Private Claims \_\_\_\_\_

Rodney D. Unema, in a field survey on Nov. 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

1. Description of original monument and accessories and/or subsequent restoration:

K-10 1/4 Corner between Sections 25 and 26  
Original gov't corner set in Dec. 1831  
by Sylvester Sibley  
Set H.W.P.  
Maple 12" N70°E 27 links  
Maple 4" S74 1/2°W 55 links

L.C.R.C. Liber 1, Page 279 (Feb. 15, 1972)  
Set 3/4" pipe midway on line  
Nail in face of 10" Poplar NW 37.32'  
Nail in face of P.P. SW 58.47'  
Nail in face of street sign E 15.87'  
Nail in face of SE hse cor WNW 72.21'  
Nail in face of 30" Beech SSW 77.26'

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10  
Found 3/4" solid iron in Mon. box  
C/L of N-S B.T. road (8th Avenue) West 6.5'  
C/L of gravel road to West South 6.5'  
SE house corner N75°W 72.10'  
Found nail in N side 14" Cherry S80°E 41.12'

Accepted as a careful perpetuation of the position of the original corner, and placed a Std. O.C. Cap on existing 3/4" solid iron rod in Mon. Box.

F.A. 345 OTTAWA COUNTY

PEER APPROVED 11/26/94

3. Description of monument for corner and accessories established to perpetuate locating the position of the cap:

K-10 1/4 Corner Common to Sections 25 and 26  
Std. O.C. cap on 3/4" iron rod in Mon. box  
C/L of N-S B.T. Road (8th Avenue) West 6.5'  
C/L of gravel road to West South 6.5'  
SE corner of house #1205 fndn. N75°W 72.10'  
Set nail & O.C. tag in N side 14" Cherry S80°E 41.12'  
Set nail & O.C. tag in NE side 12" Spruce N34°W 49.27'  
Set 1/2" rered 1.0' SE of street sign S39°W 56.44'



Signed by Rodney D. Unema  
Surveyor's Michigan License No. 33987

Date Nov. 17, 1994