

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
94 DEC 15 AM 11:48

John C. Bueche
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>13W</u>	<u>K-13 (SE, 35)</u>
	T _____ R _____	<u>Jamestown Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on December 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-13 GLO	LCRC L3-P370	LCRC-L3 P185, Allegan Co., Apr., 1978	T.K.A.
Set post	July, 1979		No date
Beech 6" N 15° W 28 lks	3/4" solid iron SW cor. conc.	1" solid iron Nail in SW side PP	1" pipe, boat spk @ surface
Beech 7" N 62° E 49 lks	hdwl. SSW 37.65'	N 55° W 77.95'	SW cor. conc.
Jan., 1832	Nail on SW side PP NW 78.00'	SE cor. conc. hdwl. N 20° W 35.22'	blk. bldg.
L. Lyon, D.S.	NW cor. conc. hdwl. NNW 42.65'	NE cor. conc. hdwl. S 30° E 35.10'	Road sign
			N 45° E 56.2'
			TP N 45° W 60.67'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

K-13 Found 1" x 24" solid iron
Nail in SW side PP
N 55° W 77.95'
SE cor. conc. hdwl.
N 20° W 35.22'
NE'ly cor. hse. fdn.
S 65° W 145.60'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

K-13 Replaced 1" solid iron with 3/4" x 24" pin with Allegan Co. Remon. Cap
Nail & Allegan Co. Remon. Tag in W side PP S 30° W 163.49'
Nail & Allegan Co. Remon. Tag in SW side PP N 45° W 78.05'
NE'ly cor. hse. fdn. S 65° W 145.58'
SE cor. conc. hdwl. N 10° W 35.22'
C/L gravel N-S E 4'±
C/L gravel E-W N 2'±



Signed by John C. Bueche

Date 12-12-94

Surveyor's Michigan License No. 13027

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983