

DEC 01 1993

COMMISSION

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 NOV 11 AM 11:56

REGISTER OF DEEDS OTTAWA COUNTY, MI

For corners in Ottawa (County)

Located In: Corner Code #

Jamestown Township

- 1. Public Land Survey T 5N R 13W L-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

I, Rodney D. Unema, in a field survey on October 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-3 1/4 corner between Sections 1 and 12 L.C.R.C. Liber 5, Page 352 (Dec. 1988) Cast iron Mon. Set CIM 10" Cherry NE 34.94' 18" Cherry SW 48.15' 14" Oak SSW 28.88'

L.C.R.C. Liber 1, Page 325 (April 1972) "T" iron Nail in sde 18" W. Cherry N 25.0 Nail in sde 12" W. Cherry WNW 90.3 Nail in sde 12" W. Cherry SW 47.8 Nail in sde 36" Oak S 102.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3 Found O.C. Cast iron Mon. 1" below surface of gravel road Found spike in W sde 14" Oak S25°W 29.07' Found spike in NW sde 20" Cherry S63°W 49.15' Found spike in NW sde 10" Cherry N49°E 34.94'

Accepted as a careful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 1/4 corner between Sections 1 and 12 O.C. cast iron Mon. (1" below gravel surface) C/L of E-W gravel road (Quincy) South + 1.0' O.C. tag & nail in W sde 14" Oak S25°W 29.07' O.C. tag & nail in NW sde 20" Cherry S63°W 48.53' O.C. tag & nail in NW sde 10" Cherry N49°E 34.96' "X" in top conc. headwall at W end culv. N56°W 36.38' Old fence line to North, tree row to South



Signed by Rodney D. Unema

Date November 4, 1993

Surveyor's Michigan License No. 33987