

**SURVEY &  
REMONUMENTATION**

APR 25 1995

OTTAWA COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12: 29

**COMMISSION**

*Robert S. Ballman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in  
Ottawa

(County)

Located In:  
Jamestown Township

Corner Code #

1. Public Land Survey	T	5N	R	13W	L-9
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

1. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
2. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Rodney D. Unema, in a field survey on Nov. 7, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

1. Description of original monument and accessories and/or subsequent restoration:

L-9 1/4 Corner between Sections 24 and 25  
Original gov't corner set in Dec. 1831  
by Sylvester Sibley  
Set 1/4 Section post  
Beech 6" 53°W 7 links  
Sugar 18" N24°W 23 links

L.C.R.C. Liber 3, Page 2 (Dec. 11, 1975)  
Found 1/2" round iron  
T.Pole (PK in W side) N 21.10'  
P.Pole (PK in E side) S 52.71'  
SW corner garage NW 165.32'

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9  
Found 1/2" solid iron (bent) + on C/L of E-W gravel road  
Held base of bent 1/2" iron by existing witnesses.  
Found nail & bottle cap in E side T.Pole North 21.10'  
Found nail & bottle cap in E side P.Pole South 52.74'  
SW corner garage (brick) N42°W 165.32'

Accepted position of 1/2" iron (base) as a careful perpetuation of the position of the original corner and replaced with Std. O.C. Cap on 24" x 3/4" iron rod.

PA. 345 OTTAWA COUNTY

PEER APPROVED 11/21/94

C. Description of monument for corner and accessories established to perpetuate location and position of the corner:

L-9 1/4 Corner between Sections 24 and 25  
Std. O.C. Cap on 24" x 3/4" iron rod  
Top of cap is 6" below gravel surface  
SW corner of garage (brick)  
Set nail & O.C. tag in E side T.Pole  
Set nail & O.C. tag in N side 24" Walnut  
Set nail & O.C. tag in E side P.Pole  
Fence lines to South and North

N42°W 165.32'  
North 21.10'  
S78°E 123.16'  
South 52.74'



Signed by Rodney D. Unema

Date Nov. 17, 1994

Surveyor's Michigan License No. 33987