

**Ottawa County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

97 JUL 24 PM 2:21

For corners in  
Ottawa  
(County)

Located In: Corner Code #

- |                                    |                          |   |
|------------------------------------|--------------------------|---|
| 1. Public Land Survey              | T <u>5N</u> R <u>13W</u> | <u>L-13 (S<math>\frac{1}{4}</math>, 36)</u> |
|                                    | T _____ R _____          | <u>Jamestown Twp.</u>                       |
|                                    | T _____ R _____          | _____                                       |
|                                    | T _____ R _____          | _____                                       |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____                                       |
|                                    | S _____ T _____ R _____  | _____                                       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____                                       |
|                                    | S _____ T _____ R _____  | _____                                       |

*Edythe Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John C. Bueche, in a field survey on April 18, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

L-13 GLO, 1831 Lucius Lyon, DS Set H.M.P. Beech 18 N 74 E 39 Beech 4 N 27 W 24	L882, P654 Allegan. Co. CP Co. Set cor. 1976 2650.28' East & West on Line SE 36 & SW 36 are common (5300.56' total) Same wt. as L2, P360	LCRC L2, P360 Allegan Co., Jan., 1975 Set rebar 1/2 distance & on sec. line TP N 20° E 29.74' Rd. sign N 40° E 28.00' PP S 40° E 70.90' SE cor. garg. N 5° W 55.93' (See sketch on back)
--	--	--

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-13 Found PK 0.20' S & 0.30' E of point; common corner S 1/4 36, 5-13 & N 1/4, 4-13  
Meas. 5299.97' set corner 1/2 distance on line between SE 36 & SW 36 (both corners are common)  
Meas. West 2649.98' to SW 36 (CP 2650.28')  
Meas. East 2649.98' to SE 36 (CP 2650.28')  
PP S 40° E 70.90'±  
SE cor. garg. N 5° W 55.93'±

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 4/21/97

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-13 Set Allegan Co. Mon. (3/4" x 24" Pin with Cap) in bit. road  
Nail & Ottawa Co. Remon. Tag in S side PP N 70° W 147.05'  
Nail & Ottawa Co. Remon. Tag in E side 10" Elm N 07° E 45.24'  
Nail & Ottawa Co. Remon. Tag in SW side Pp S 32° E 71.22'  
NE cor. wood fnd. to bldg. S 36° W 77.85'  
NW cor. wood fnd. to bldg. S 56° W 113.30'  
SE cor. hse. frame N 05° W 55.49'  
On C/L bit. E-W; on fence North; C/L gravel South, East 10'±

Signed by John C. Bueche  
John C. Bueche, P.S. 13027  
Surveyor's Michigan License No. \_\_\_\_\_

Date 5-29-97

