

SURVEY & REMONUMENTATION

FEB 27 1998

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **SECTION**
Ottawa
(County)

Located In: Jamestown Twp. Corner Code #
T 5N R 13W M-2
T _____ R _____ E 1/4, Sec. 1
T _____ R _____
T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

RECORDED

97 OCT 30 AM 11:00

Debra Gant

**Register of Deeds
Ottawa County, MI**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	5		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Rodney D. Unema, in a field survey on August 11, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-2 E 1/4 Corner, Section 1
Oct. 1831 - Original Gov't. LCRC Lib. 2, Pg. 95 (4-5-73)
Corner set by Lucius Lyon Found RR Spike
Set H.W.P. Nail in side P. Pole NW 58.86'
Beech 30 Corner Nail in side T. Pole W-SW 163.95'
Nail in side T. Pole S-SW 171.88'

LCRC Lib. 5, Pg. 348 (12-6-88)
Set C.I.M.
PK in Guy Pole SE 68.24'
RR Spk in PP SE 52.12'
PK in Guy Pole SSE 69.57'
Center Stop Sign SW 48.36'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2 Found 4" Diameter C.I.M. in Mon. Box @ Intersection Kenowa & Ransom
Found PK Nail in SW side P. Pole S40°E 52.12'
Found PK Nail in SW side Guy Pole S27°E 69.59'
Found PK Nail in NE side Guy Pole S52°E 68.24'
φ Stop sign S68°W 48.46'
Kent Co. Corner A-2 North 173.09'

**P.A. 345 OTTAWA COUNTY
PEER APPROVED 9-15-97**

[Signature]

Accepted as a careful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 E 1/4 Cor., Sec. 1
4" Dia. Harrison Mon. in Mon. Box
On φ of Ransom Road (B.T.) to West
φ Kenowa Ave. (N-S B.T.) East 2.0'
Set Nail & O.C. Tag in SW side P. Pole S40°E 52.56'
Set Nail & O.C. Tag in joint of curb S44°W 37.08'
Set Nail & O.C. Tag in E side Guy Pole N11°W 94.89'
Kent Co. Mon. (A-2) North 173.09'



Signed by Rodney D. Unema
Surveyor's Michigan License No. 33987

Date August 15, 1997