

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED 1307
96 DEC 18 PM 4:56

Randy D. Feenstra
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in
Ottawa

Located In:	Corner Code #
Jamestown Twp.	M-6, E 1/4 cor.
T 5N R 13W	Sec. 13
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

Register of Deeds Stamp & File Number

1. Public Land Survey

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randal D. Feenstra, in a field survey on Dec. 9, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Hardwood Post	L-4, P-149, Capped Rod	
Lucius Lyons, (1831)	Iron North	142.05'
10" Beech N65°W 7 lks.	Nail in Side P. Pole W	32.76'
16" Beech S29°W 39 lks.	Nail in Side P. Pole NE	29.65'
	Nail in Side 16" Maple SSW	90.81'
	Nail in Side 14" Maple NNE	73.59'

Kent County
From L.C.RC #5704 Ottawa County Corner
is South 142.3' from Kent County Monument

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Found: Rebar in patch on road		
Found Kent County Monument	N	142.07
Nail and Tag in N Side P.Pole	W	32.91

Accepted as a careful and faithful perpetuation of the position of the original corner

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12-9-96



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 Set Remon Bar and Cap in New Monument Box		
Ottawa County Remon Tag and Nail in N side P. Pole	Az. 269°	32.91'
Ottawa County Remon Tag and Nail in SE side 9" Maple	Az. 218°	81.82'
Ottawa County Remon Tag and Nail in W side P. Pole	Az. 168°	125.48'
Ottawa County Remon Tag and Nail in S side 24" Multiple Maple	Az. 84°	43.61'
Centerline N/S Bit. Road W 1.3' (Kenowa Ave.)		
Kent County Monument (A-6 Byron Twp.)	N	142.07'

Signed by Randal D. Feenstra

Date December 9, 1996

Surveyor's Michigan License No. 37275

