

**SURVEY &
REMONUMENTATION**

APR 25 1995

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:29

COMMISSION

For corners in

Philip Carlsson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

| | | |
|---------------------------------------|-------------------------|---------------|
| Ottawa <small>(County)</small> | Located In: | Corner Code # |
| | Jamestown Township | |
| 1. Public Land Survey | T 5N R 13W | M-9 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Rodney D. Unema, in a field survey on Nov. 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | |
|--|--|--|
| M-9 Corner Common to Sections 24 and 25 | | |
| Original gov't corner set on Oct. 18, 1831 by Lucius Lyon. | L.C.R.C. Liber 1, Page 279 (Feb. 15, 1972) | L.C.R.C. Liber 3, Page 2 (Dec. 11, 1975) |
| Set post | Found iron pipe | Found 3/4" round iron |
| Beech 9" S50°W 48 links | Nail in face of PP NE 30.49' | Sq. spk in SE side 20" Walnut |
| Beech 6" N34°W 13 links | Nail in face of PP SW 67.76' | SW 32.85' |
| | Nail in face of 24" Walnut | C/L Street sign WSW 28.30' |
| | SW 32.38' | "T" iron 1' S of stop sign |
| | | NNE 21.49' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9
Found 3/4" iron in gravel road at intersection of Kenowa Ave. and Perry
Found nail in SE side 24" Walnut S54°W 32.82'
C/L street sign S77°W 28.4'
Found nail & bottle cap in SE side PP S50°W 67.85'

Accepted position of 3/4" iron as a careful perpetuation of the position of the original corner and replaced with Std. O.C. Cap on 24" x 3/4" iron bar.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/21/94
Michael J. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | |
|--|---------------|
| M-9 Corner Common to Sections 24 and 25 | |
| Std. O.C. Cap on 24" x 3/4" iron bar (6" below surface of gravel road) | |
| SW cor., Section 19, T5N, R12W, Kent County Remon | North 75.90' |
| Set nail & O.C. tag in N side PP | S79°E 126.87' |
| Set nail & O.C. tag in SE side 24" Walnut | S54°W 32.82' |
| Set nail & O.C. tag in E side 18" Apple | S15°W 106.33' |
| on C/L of gravel roads to South and West | |



Signed by Rodney D. Unema Date Nov. 17, 1994
Surveyor's Michigan License No. 33987