

SURVEY & REMONUMENTATION

DEC 16 1996

OTTAWA COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ottawa

(County)	Located In:	Corner Code #
	Jamestown Twp.	M-12, E1/4 cor.
1. Public Land Survey	T <u>5N</u> R <u>13W</u>	Sec 36
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED
96 NOV 14 AM 11:21
R. J. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randal D. Feenstra, in a field survey on Oct 10, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|------------------------|--------------------------------|--|
| G.L.O. Hardwood Post | L-1, P-379, Cast Iron Monument | L-3, P-359, Cast Iron Monument |
| Lucius Lyons, (1831) | Nail in P. Pole SW 33.13' | Spike in side 8" Apple WSW 43.19' |
| 18" Beech N74°E 39 lks | Nail in 6" Apple NW 42.95' | Spike in side 10" Cherry NW 47.63' |
| 4" Beech N27°W 24 lks | St. sign NE 52.10' | PK in side P. Pole NE 121.87' |
| | Centerline St. Sign SW 30.30' | Approx. centerline 104th/Kenowa North 28'± |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12 Found: Cast Iron Monument in Gravel

Spike in 12" Cherry Az. 331° 48.18'



Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-12 Cast Iron Monument in Gravel Road
- Ottawa County Remon Tag and Nail in NW side P. Pole Az. 36° 119.76'
- Ottawa County Remon Tag in SW side 10" Cherry Clump Az. 155° 62.28'
- Ottawa County Remon Tag in NW side P. Pole Az. 244° 53.90'
- Ottawa County Remon Tag in NE side 12" Cherry Az. 331° 48.18'
- Kent County Monmment N 30.39' (also centerline bit. road to E)
- Centerline Gravel road N/S 1.5' ± W of Kenowa Ave.
- Centerline Gravel road W 5' S of Mason St.

OTTAWA COUNTY
PEER APPROVED 10-21-96
[Signature]

Signed by Randal D. Feenstra
Surveyor's Michigan License No. 37275

Date October 10, 1996