

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ottawa

Located In: Jamestown Twp. Corner Code # M-13, SE cor.
5N 13W
 T R
 T R Sec. 36
 T R
 T R
 S T R
 S T R
 S T R
 S T R

1. Public Land Survey

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECORDED
96 DEC 17 AM 10:43

Randal D. Feenstra
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Randal D. Feenstra, in a field survey on Oct 10, 1996 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Post Lucius Lyons, (1831) 10" Beech S71°E 41 lks 13" Beech N22°E 28 lks	L-1, P-135, (1971) "T" Iron 18" Walnut NE 37.90' P. Pole NW 43.20' Centerline St. sign SW 31.60'	Corner common with Kent County Monument - Certificate #4634 Nail & Tag in W side 14" Walnut N20°E 43.73' SW Cor. Hse. Fndn. N25°W 34.90' NE Cor. Hse. Fndn. S25°W 156.50' SE Cor. Conc. Hdwl. N15°E 33.58' NW Cor. Hse. Fndn. S30°W 100.37' SW Cor. Hse. Fndn. S25°W 120.30'
---	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13 Found: Kent County Monument	Az 159°	79.34'
PK & Kent County & A.C. Remon. Tags W Side P. Pole	Az 26°	43.60' (Allegan 43.57')
Kent County & A.C. Remon Tags W Side 16" Walnut	Az 64°	62.39'
PK and Kent County Remon Tag S Side P. Pole	N25°W	34.86'
SW Cor. Conc. Headwall	S25°W	156.50'
NE Cor. Hse. Fndn.	N25°E	33.56'
SE Cor. Conc. Headwall	S30°E	100.35'
NW Cor. Hse. Fndn.	S25°E	120.36'
SW Cor. Hse. Fndn.		

Accepted as a careful and faithful perpetuation of the position of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 Kent County Monument in Bit. Road	Az. 26°	43.60'
Ottawa County Remon Tag and Nail in W side 16" Walnut	Az. 64°	62.39'
Ottawa County Remon Tag in S side P. Pole	Az. 159°	79.34'
Ottawa County Remon Tag in W side P. Pole	Az. 220°	40.23'
Ottawa County Remon Tag & PK in W end 18" CMP		
Centerline E/W Bit. Road S 3' (Ottagan St.)		
On Centerline Gravel road to S 24th St.		
Centerline Gravel road to N 2' W (Kenowa Ave.)		

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11-11-96

R.D.F.



\$ 9.00 CORNER
\$ 1.00 PHOTO

Signed by Randal D. Feenstra
Surveyor's Michigan License No. 37275

Date October 10, 1996