

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:37

Dorothy Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

or corners in
Ottawa

(County)

Located In:

Corner Code #/

| | | | | | |
|---------------------------------|---|----|---|-----|--------------|
| Public Land Survey | T | 5N | R | 14W | C-7 (SE, 18) |
| | T | | R | | Zeeland Twp. |
| | T | | R | | |
| | T | | R | | |
| Property Controlling in Section | S | | T | R | |
| Miscellaneous Property in Sec. | S | | T | R | |

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

John C. Bueche, in a field survey on October 25, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

OTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- | | |
|-----------------------|---------------------------|
| C-7 GLO March, 1832 | LCRC L5-P364 |
| Calvin Britain, D.S. | 1 1/4" iron, March, 1989 |
| Set cor. | PK SE side PP ENE 78.02' |
| Beech 5 S 13 E 29 | PK SW side PP SE 57.20' |
| Sycamore 2 N 17 W 14 | Nail NW side PP SW 75.40' |
| LCRC L1-P187 | PK SW side PP WNW 77.17' |
| T iron, Dec., 1971 | |
| CP pole N 40 W 65.45' | |
| CP pole N 90 W 28.57' | |
| Fe post S 23 W 88.48' | |

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7 Found 1 1/4" iron in conc. in Mon. Box

All wit. gone

And is accepted as careful and faithful perpetuation of the position of the original corner.


John C. Bueche
REGISTER OF DEEDS
OTTAWA COUNTY
PEER APPROVED 11/21/94

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|----------------|
| C-7 Placed Ottawa Co. Alum. Cap in conc. on top of 1 1/4" iron | |
| Nail & Ottawa Co. Remon. Tag in E side PP | N 25 E 80.27' |
| Nail & Ottawa Co. Remon. Tag in W side PP | N 15 W 79.83' |
| Nail & Ottawa Co. Remon. Tag in W side PP | S 25 E 71.97' |
| Nail & Ottawa Co. Remon. Tag in S side PP | S 70 W 127.63' |
| Face of cor. fence post | S 40 W 76.35' |
| Face of cor. fence post angle point | N 50 W 70.72' |
| C/L bit. N-S & E-W | |
| PK 1.00' W & 1.00' S | |

Signed by John C. Bueche
Surveyor's Michigan License No. 13027

Date 11-18-94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983