

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE DEC 15 AM 11:48
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

Ottawa

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|----|---|-----|----------------------------|
| 1. Public Land Survey | T | 5N | R | 14W | C-8 (E $\frac{1}{2}$, 19) |
| | T | | R | | <u>Zeeland Twp.</u> |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Phyllis Kellman
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on December 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-8 GLO March, 1832	LCRC L5-P363
Calvin Britain, D.S.	3/4" iron, March, 1989
Set post	W 27.08' Nail & MSHD Tag N side PP
Beech 18 N 16 E 8	NE 49.93' C/L hydrt.
Beech 10 S 66 W 22	SE 68.73' Nail & MSHD Tag NE side PP
LCRC L3-P4	NNE 102.12' Nail & MSHD Tag W side
3/4" iron, Dec., 1975	28" "M"
SW cor. porch NE 101.35'	NE 101.35' SW cor. porch
SE cor. garg. fnd. WNW 107.4'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8 Found 1/2" rerod in bit. rd.
 SW cor. porch NE 101.35' NE 49.93' C/L hydrt.
 SE cor. garg. fnd. WNW 107.4'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 12/12/94
Wesley D. Newbold

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


C-8 Placed 1/2" rerod with Ottawa Co. Mon. (3/4" x 24" Pin with Alum. Cap) in Mon. Box

SW cor. conc. porch	N 50 E	101.29'
SE cor. garg.	N 75 W	107.22'
Nail & MSHD Tag in NE side PP	S 45 E	68.81'
Nail & MSHD Tag in S side PP	N 80 W	26.92'
SW cor. brick garg.	S 25 E	143.31'
Nail & Ottawa Co. Remon. Tag in N side PP	S 85 W	29.17'

On C/L bit. N-S
 C/L bit. East, S 1.5'±

Signed by John C. Bueche
 John C. Bueche
 Surveyor's Michigan License No. 13027

Date 12-12-94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 25, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983