

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

Ottawa County Remonumentation LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:53

For corners in

Ottawa

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|----|---|-----|---------------|
| 1. Public Land Survey | T | 5N | R | 14W | C-11 (SE, 30) |
| | T | | R | | Zeeland Twp. |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Rhonda Kullback
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on December 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-11 GLO March, 1832	LCRC L1-P133	LCRC L2-P355
Calvin Britain, D.S.	T iron Nov., 1971	T iron in Mon. Box, Oct., 1973
Set cor. in brook		Nail in Last G. post N rail N 30 E 26.8'
Maple 10 S 45 W 18		SE cor. conc. curb on bridge S 80 W 54.9'
Sycamore 12 N 70 E 20		NE cor. conc. curb on bridge N 80 W 32.3'
		OVER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11 Found T iron 0.07' E of W inside edge of Mon. Box
SE cor. conc. curb on bridge S 80 W 54.9'
NE cor. conc. curb on bridge N 80 W 32.3'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94

Harold D. Nedewell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 Replaced T iron with Ottawa Co. Mon. (3/4" x 24" Pin with Alum. Cap) in Mon. Box that was moved
PK in top of guard post N 30 W 20.12'
E end of bridge N 90 W 42.5'
Nail & Ottawa Co. Remon. Tag in top guard post N 70 E 34.25'
Nail & Ottawa Co. Remon. Tag in top guard post N 80 W 49.86'
Nail & Ottawa Co. Remon. Tag in top guard post S 50 E 38.80'
C/L bit. E-W, N 0.5'±

Signed by John C. Bueche
Surveyor's Michigan License No. 13027

Date 12-12-94



