

RECORDED

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE 97 JUL 24 PM 2: 23
Filing Requirement of Act 74, Mich. P.A. 1970

Robert B. Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in
Ottawa
(County)

Located In:	Corner Code #
T <u>5N</u> R <u>14W</u>	<u>D-13 (S$\frac{1}{2}$, 32)</u>
T _____ R _____	<u>Zeeland Twp.</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John C. Bueche, in a field survey on April 1, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13	Allegan Co. Survey LCRC L1, P 159
GLO Nov., 1831	L949, P414
Lucius Lyon, DS	Ottawa Co. East
Set HMP	74.91'
Hemlock 7 N 65 W 8	Nail in face 8" Ash WNW 75.74'
Beech 10 N 56 E 35	Nail in face TP NE 33.84'
	Nail in face 15" Maple SE 31.35'
	St. sign post NE 29.89'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 Found 1/2" rerod in Mon. Box
 All wit. gone Allegan Co. cor. (N $\frac{1}{2}$ 5, 4-14) West 74.90'
 Dist. West 2641.90'
 Dist. North 2628.97' to South Mon. Box (also Mon. Box 5' N)
 Dist. East 2641.50'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Allegan Co. Meas. 2669.35 + 2668.74 = 5338.09 (HEI Meas. 1979)
 Meas. Ottawa Co. 5283.40 - 102.30 + 47.52 = 5283.31 (Meas. 5283.40)
 No occupation North @ 1/8 line East or West of corner

RA. 345 OTTAWA COUNTY


PEER APPROVED 6-16-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 Replaced 1/2" rerod with Ottawa Co. Mon. (3/4" x 24" pin with alum. cap)
 Nail & Ottawa Co. Remon. Tag in N side 8" Ash S 43° W 55.87'
 Nail & Ottawa Co. Remon. Tag in N side 8" W. Cherry S 14° W 63.02'
 Nail & Ottawa Co. Remon. Tag in W side TP S 20° E 52.30'
 Nail & Ottawa Co. Remon. Tag in top of fence post N 53° W 49.32'
 C/L bit. E-W, South 1'±
 C/L bit. West 3'±
 Overisel cor. West 74.9'

Signed by John C. Bueche
 John C. Bueche, P.S.
 Surveyor's Michigan License No. 13027

Date 4-16-97



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN. 25, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983