

**Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>14W</u>	<u>E-2 (W 1/4, 4)</u> <u>Zeeland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

96 DEC 17 AM 10:41

Phyllis Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John C. Bueche, in a field survey on October 17, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-2 GLO	LCRC L1, P231	LCRC L3, P399, 1979
Calvin Britain, DS, 1832	Fnd. steel rod 1972	Fnd. rebar with stone below
Set 1/2 mile post	Nail in face of PP	Set cast iron mon.
Beech 10 N 65 E 12	SE 90.97'	C/L tel. box SW 40.13'
Beech 7 S 65 W 30	Nail in face of TP	C/L tel. box SW 38.29'
	SW 40.74'	C/L st. sign SE 43.60'
	Nail in face of fence	C/L PP SE 91.4'
	post NW 33.26'	
	St. sign SE 43.49'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-2 09/17/96 during construction
Dug a trench 1.5'± wide; 2'± deep; 6'± long; found pointed stone down 2'±, set capped JCB iron on top of stone
Nail in face of PP
SE 90.97'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

STATE OF MICHIGAN
OTTAWA COUNTY

PEER APPROVED 11-11-96

J.P.N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-2 Set Ottawa Co. Mon. (3/4" x 24" pin with cap) in Mon. Box
Ottawa Co. Remon. Tag & Nail on N side PP S 53° E 91.48'
Capped iron (JCB) S 40° W 40.01'
Top C/L 15" CMP N end N 73° E 81.97'
C/L Bell Box S 44° W 39.97'
C/L Bell Box S 38° W 41.17'
On C/L X of gravel rds. N-S, E-W
C/L water valve box N 77° E 31.68'

\$ 9.00 CORNER
\$ 1.00 PHOTO



Signed by John C. Bueche
John C. Bueche, P.S. 13027
Surveyor's Michigan License No. _____

Date 11-7-96