

REMONUMENTATION

1993

COMMISSION

Ottawa County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 DEC 15 AM 9:25

*Phyllis Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>14W</u>	<u>E-4 (E 1/4, 8)</u> <u>Zeeland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John C. Bueche, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

E-4 LCRC (L5, P101), Dec. 22, 1983 3/4" iron PK in N side PP E 75.20' Spk. in NE side 18" Ash SE 40.30' Spk. in S side fe. post W 27.55' SW cor. hse. NE 153.53'	E-4 LCRC (L2, P673), Oct. 22, 1974 3/4" iron 20" Box Elder SE 39.50' PP E 74.81' Cor. fe. post W 27.00'	E-4 LCRC (L1, P161), Dec. 10, 1971 3/4" pipe S 55° E 39.53' 20" Maple West 27.00' fe. cor. post East 74.80' PP
--	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4 Found 3/4" pipe & rerod 0.20' W in gravel road PK in N side PP E 75.20' Spk. in NE side 18" Ash SE 40.30' SW cor. hse. NE 153.53' C/L gravel road E 3'± On fe. line to W	20" Box Elder SE 39.50' PP E 74.81'	S 55° E 39.53' 20" Maple East 74.80' PP
--	--	--

And is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4 Replaced 3/4" pipe with Std. O.C. Mon. (3/4" x 24" Pin & Cap), down 6"±

Conc. Nail & O.C. Remon. Tag in N side 12" Scyamore	N 50° E 63.42'
Conc. Nail & O.C. Remon. Tag in N side 24" Maple	S 45° E 40.30'
Conc. Nail & O.C. Remon. Tag in N side 6" Elm	S 75° W 25.02'
Conc. Nail & O.C. Remon. Tag in N side PP	N 90° E 75.20'
SW cor. brick hse.	N 60° E 153.53'

C/L gravel road N-S, E 3'±  
On fence lines E & W

Signed by John C. Bueche  
Surveyor's Michigan License No. 13027

