

**SURVEY &  
REMONUMENTATION**

APR 25 1995

**COMMISSION** Ottawa County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:37

*Elizabeth Waldman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

corners in Ottawa (County)	Located In:	Corner Code #
Public Land Survey	T <u>5N</u> R <u>14W</u>	<u>E-9 (SE, 20)</u> <u>Zeeland Twp.</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
Property Controlling in Section	S ___ T ___ R ___	___
Miscellaneous Property in Sec.	S ___ T ___ R ___	___

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

John C. Bueche, in a field survey on October 20, 19 94,  
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

E-9 GLO March, 1832	LCRC L3-P294
Calvin Britain, D.S.	CIM, Sept., 1978
Set cor.	PK in PP ENE 184.80'
Maple 7 N 85 W 23	14 Tree NW 263.20'
Maple 7 S 24 E 43	C/L ditch N 4'±
	C/L rd. South

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9 Found Ottawa Co. Mon. (4" Harrison)  
C/L ditch N 4'±  
C/L rd. South

And is accepted as a careful and faithful perpetuation of the position  
of the original corner.

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 11/21/94

*Madison D. Hedewell*



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9 Ottawa Co. Mon. (4" Harrison)	
Nail & Ottawa Co. Remon. Tag in N side PP #1089	S 80 E 206.80'
Nail & Ottawa Co. Remon. Tag in SE side PP	S 80 W 51.85'
C/L N-S river (30' wide)	W 270'±
On fence line E,	E 300'±
C/L rd. (2 track)	S 2640'±
C/L Power Line E-S,	S 12'±
C/L 2 track N-S	W 200'±

signed by John C. Bueche Date 11-18-94  
Surveyor's Michigan License No. 13027