

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:38

Richard R. Adams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

or corners in
Ottawa

(County)

Located In:

Corner Code =#

Public Land Survey	T	<u>5N</u>	R	<u>14W</u>	<u>E-10 (E$\frac{1}{2}$, 29)</u>
	T	_____	R	_____	<u>Zeeland Twp.</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
Property Controlling	S	_____	T	_____	_____
in Section	S	_____	T	_____	_____
Miscellaneous	S	_____	T	_____	_____
Property in Sec.	S	_____	T	_____	_____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

John C. Bueche, in a field survey on October 14, 1994,
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Description of original monument and accessories and/or subsequent restoration:

E-10 GLO March, 1832	LCRC L3-P288
Calvin Britain, D.S.	CIM, Sept., 1978
Set post	8 Chinese Elm SE 86.98'
Elm 10 S 65 E 19	PP SSE 160.05'
Black Ash 5 N 65 W 21	14 Ash NW 21.33'
	Field line to West
	C/L ditch E 14'±

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10 Found Ottawa Co. Mon. (4" Harrison) in C/L 2 track down 1'±	
PP	SSE 160.05'
14 Ash	NW 21.33'

And is accepted as a careful and faithful perpetuation of the position
of the original corner.

P.A. 345 OTTAWA COUNTY

PEER APPROVED 11/21/94
Richard D. Hedewell

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10 Ottawa Co. Mon. (4" Harrison)	
Nail & Ottawa Co. Remon. Tag in E side 24" Ash	N 15 W 21.20'
Nail & Ottawa Co. Remon. Tag in E side PP 5'± above ground	S 7 E 160.46'
Nail & Ottawa Co. Remon. Tag in top of wood fence post	S 55 E 69.13'
C/L ditch	E 14'±
S end of bolt on lower brace to PP 8'± above ground	N 60 W 314.81'
Power line running N 40 W	S 0 E 130'±

Signed by John C. Bueche
Surveyor's Michigan License No. 13027

Date 11-18-94

