

SURVEY & REMONUMENTATION

APR 24 1995

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE

RECORDED

94 DEC 15 AM 11:49

For corners **COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

Phyllis Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

<u>Ottawa</u> <small>(County)</small>	Located in:	Corner Code #	
1. Public Land Survey	T <u>5N</u> R <u>14W</u>	<u>E-11 (SE, 29)</u>	
	T _____ R _____	<u>Zeeland Twp.</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John C. Bueche, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-11 GLO March, 1832	LCRC L1-P57 RR spk., June, 1971	LCRC L3-P116 RR spk., Oct., 1976
Calvin Britain, D.S.	Nail in face 48" Sycamore SW 88.88'	PK in NE side PP SE 38.77' Spk. in E side 36" Tree
Set cor. W Oak 10	Nail in face PP SE 38.28' Nail in face 15" Maple	SSW 90.90' Spk. in NE side 20" W. Cherry
S 80 E 19	NE 49.11'	NW 52.52'
Ironwood 7	Nail in face 18" Cherry	Spk. in NW side 20" Maple
N 89 W 18	NW 51.63'	NE 49.97'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11 Found	4" below surface	
	Nail in face 48" Sycamore	PK in NE side PP SE 38.77'
	SW 88.88'	Spk. in NW side 20" Maple
	Nail in face 15" Maple	NE 49.97'
	NE 49.11'	

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Wesley D. Hedrick

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


E-11 Replaced RR spk. with Ottawa Co. Mon. (3/4" x 24" Pin with Alum. Cap) in Mon. Box.

Nail & Ottawa Co. Remon. Tag in N side 12" Elm	N 50 W 76.40'
Nail & Ottawa Co. Remon. Tag in SE side PP	S 60 W 72.66'
Nail & Ottawa Co. Remon. Tag in SW side PP	S 30 E 52.33'
Nail & Ottawa Co. Remon. Tag in N side 20" Maple	N 40 E 50.18'

C/L bit. E-W, N 2.5'+
On C/L bit. South, on C/L gravel N

Signed by John C. Bueche
Surveyor's Michigan License No. 13027

Date 12-12-94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983