

RECORDED

97 JUL 24 PM 2:25

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ottawa
(County)

Located In: Corner Code #

- 1. Public Land Survey T 5N R 14W G-2 (W $\frac{1}{2}$, 3)
T _____ R _____ Zeeland Twp.
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Rhonda Ballman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on April 1, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		▲	3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-2	LCRC L1, P233	LCRC L5, P261
GLO April, 1832	Iron pipe, Jan., 1972	Set CIM Aug., 1986
Calvin Britain, DS	Nail in face TP NW 48.20'	30" Maple SW 77.60'
Set 1/2 mile post	Nail in face 12" Maple	NW cor. church fnd. SE 76.71'
Sugar 4 N 34 E 4	SW 100.40'	PP NE 54.52'
Beech 9 S 60 W 17	Nail in face PP NE 54.10'	TP NW 47.25'
	NW cor. church SE 76.71'	
	NE cor. bldg. SW 56.69'	OVER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-2 Found capped rerod in Mon. Box
 Nail & Tag in SE side PP N 55° E 54.52'
 Nail & Tag in N side GP N 45° W 47.25'
 Nail & Tag in W side 32" Maple S 30° W 77.60'
 NW cor. church fnd. S 50° E 76.71'
 SW cor. church fnd. S 45° E 88.32'

PEER APPROVED 4/21/97
J.D.F.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2 Replaced rerod with Ottawa Co. Mon. (3/4" x 24" pin with alum. cap)
 Nail & Tag 14091 in SE side PP N 53° E 54.53'
 Nail & Tag 14091 in NE side cut off pole N 45° W 47.13'
 NE cor. church fnd. S 70° E 131.47'
 NW cor. church fnd. S 50° E 76.71'
 SW cor. church fnd. @ entrance S 45° E 88.32'
 On C/L bit. East, on C/L bit. N-S, C/L bit. W, North 2'±



Signed by John C. Bueche Date 4-16-97
Surveyor's Michigan License No. 13027

PART A - continued

LCRC L6, P19

Iron in Mon. Box, Dec., 1989

Nail & Tag in SE side PP N 55° E 54.52'

Nail & Tag in N side GP N 45° W 47.25'

Nail & Tag in W side 32" Maple S 30° W 77.60'

NW cor. church fnd. S 50° E 76.71'

SW cor. church fnd. S 45° E 88.32'