

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:38

Richard R. Harrison
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in
Ottawa

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>5N</u> R <u>14W</u>	G-5 (SE, 9) <u>Zeeland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

John C. Bueche, in a field survey on October 25, 19 94,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

1. Description of original monument and accessories and/or subsequent restoration:

G-5 GLO March, 1832	LCRC L1-P263 Iron pipe Feb., 1972	LCRC L4-P55 CIM, May, 1980
Calvin Britain, D.S.	Nail in face TP NE 39.30'	Wood guard post SE 36.91' Wood guard post NE 33.74'
Set cor.	Nail in face TP	Wood guard post NW 36.68'
Black Ash 10 S 23 W 20	N 75 E 91.80' S'ly 2 rivets CMP	"X" cut conc. culv. SW 31.55' C/L E end CMP NE 42.57'
Black Ash 12 N 46 E 22	NW 41.57' S'ly 2 rivets CMP NE 43.85'	C/L W end CMP NW 41.40'

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5 Found Ottawa Co. Mon. (4" Harrison) in gravel rd.	S'ly 2 rivets CMP	C/L E end CMP	NE 42.57'
	NW 41.57'	C/L W end CMP	NW 41.40'
	S'ly 2 rivets CMP		
	NE 43.85'		

And is accepted as a careful and faithful perpetuation of the position
of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/21/94
Richard P. Newell

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5 Ottawa Co. Mon. (4" Harrison)			
"X" cut in top of 36" conc. culv.	S 30 E 35.03'		
"X" cut in top of 36" conc. culv.	S 45 W 34.15'		
S'ly of 2 rivets in W end CMP	N 25 W 41.57'		
S'ly of 2 rivets in E end CMP	N 30 E 43.97' (bent CMP)		
On C/L bit. E			
On C/L gravel N-S & W			

Signed by John C. Bueche
John C. Bueche
Surveyor's Michigan License No. 13027

Date 11-18-94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983