

**SURVEY &
REMONUMENTATION**

APR 05 1996

**Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE**

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>14W</u>	G-6 (E $\frac{1}{2}$, 16)
	T _____ R _____	Zeeland Twp.
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

95 NOV 29 PM 1:42

Richard S. Holman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche, in a field survey on November 13, 19 95
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-6 GLO Calvin Britain, D.S. March, 1832 Set 1/2 mile post Beech 20 S 75 E 11 Sugar 20 S 64 W 10	LCRC L1-P351, April, 1972 Chisled cross top stone Nail set in face 16" Maple SE 57.32' Nail set in face 18" Maple SE 33.25' St. sign E 18.40' NW cor. conc. pillar SE 25.00'
--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6 Found "X" cut in top stone
St. sign E 18.40'

And is accepted as a careful faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY

PEER APPROVED 11/20/95

Richard P. McDowell
RDN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6 Set 3/4" x 24" Pin with Ottawa Co. Cap
Set Nail & Ottawa Co. Remon. Tag in SW side 40" Maple S 50 E 34.25'
Set Nail & Ottawa Co. Remon. Tag in SW side 30" Maple S 20 E 73.42'
Set Nail & Ottawa Co. Remon. Tag in SE side 10" Maple S 40 W 63.31'
Set Nail & Ottawa Co. Remon. Tag in NE side 14" Elm N 20 W 81.96'
C/L gravel rd. West, South 3'±
C/L gravel rd. N-S, West 5'±



Signed by John C. Bueche
John C. Bueche, P.S.
Surveyor's Michigan License No. 13027

Date Nov. 16, 1995