

RECORD

1993

COMMISSION

Ottawa County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 DEC 15 AM 9:31

*Deborah Kellerman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>14W</u>	<u>G-11 (SE, 28)</u> <u>Zeeland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche, in a field survey on October 13, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G-11 LCRC (L2, P737) Jan. 20, 1975  
Found 3/4" pipe 1.3' N of C/L blacktop  
PP SW 59.48'  
PP N 64.81'  
PP ESE 133.81'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-11 Found 3/4" pipe in mon. box  
PP N 64.81' Found Tag & Nail #01642 W side PP N 62.60'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11 Set O.C. Mon. & Cap in Mon. Box  
O.C. Remon. Tag & Nail in S side PP N 80° E 234.36'  
Nail & Tag #01642 in W side PP N 10° E 62.60'  
O.C Remon. Tag & Nail in E side PP S 15° W 4'± above ground 194.  
O.C. Remon. Tag & Nail on top of post @ MBT box S 43° W 62.80'  
2'± N of C/L E-W bit. road  
C/L gravel road S is 4' W  
Meas. by EDM

Signed by John C Bueche  
Surveyor's Michigan License No. 13027

Date Nov. 29, 1994

