

**SURVEY &
REMONUMENTATION**

APR 05 1996

COMMISSION

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>14W</u>	<u>G-13 (SE, 33)</u>
	T _____ R _____	<u>Zeeland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED
95 NOV 29 PM 1:42
Phyllis Hartman
REGISTER OF DEEDS
OTTAWA COUNTY, MI
Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on November 14, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-13 GLO Lucius Lyon, D.S. 1832	LCRC L2-P735, Jan., 1975	LCRC L3-P229, Dec., 1977
Set post	"T" iron	Found #80 spk. over angle iron, set cast iron mon.
Beech 7	C/L gravel rds.	
N 36 E 8	Rd. sign N 50 E 15.09'	C/L st. sign ENE 15.2'
Beech 8	TP S 80 E 28.25'	Fe. cor. post NW 22.32'
N 65 W 35	PP N 80 W 103.04'	C/L warning sign SW (no distance shown)
	Cor. fe. post N 45 W 22.30'	PP WNW 103.11'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 Found Ottawa Co. cast iron mon.
C/L st. sign ENE 15.2'
Fe. cor. post NW 22.32'
PP WNW 103.11'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

PA. 345 OTTAWA COUNTY
PEER APPROVED 11/20/95
Richard P. Hedweld

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 Ottawa Co. cast iron mon.
Set Nail & Ottawa Co. Remon. Tag in S side PP N 80 W 103.00'
Set Nail & Ottawa Co. Remon. Tag in NE side cut off PP N 40 W 22.50'
Set 1/2" rebar S 20 E 47.07'
Set 1/2" rebar N 20 E 44.73'
C/L gravel rd. N-S 2.0'± East

Signed by John C. Bueche
John C. Bueche, P.S.
Surveyor's Michigan License No. 13027

Date Nov. 16, 1995

