

SURVEY &
REMONUMENTATION

FEB 18 1994

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 NOV -8 PM 1:58

COMMISSION

Dorothy Redmond
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------------------------|
| 1. Public Land Survey | T <u>5N</u> R <u>14W</u> | H-9 (S <u>1</u> , <u>22</u>) |
| | T ___ R ___ | <u>Zeeland Twp.</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche, in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-9 (L3, P192) Sept. 23, 1977
C.I.M.
Guy pole WNW 44.24'
St. sign N 23.9'
PP SW 49.43'
Iron W 6.35'
Field line to N

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-9 Found O.C. Harrison Mon. in good condition, down 8"±
Guy pole WNW 44.24'
PP SW 49.43'
Iron W 6.35'
Field line to N

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9 O.C. Harrison Mon., down 8"±
O.C. Remon. Tag & Nail in NW side PP S 60° W 49.93'
O.C. Remon. Tag & Nail in SW side guy pole N 60° W 44.45'
O.C. Remon. Tag & Nail in E side 6" Apple N 10° W 24.27'
Top C/L gas pipeline marker N 35° E 32.45'
C/L gravel E & W is N 2'±
C/L gravel S is 7'± W
On field line to N
Meas. by hand



Signed by John C Bueche

Date Oct. 18, 1993

Surveyor's Michigan License No. 13027