

**Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Ottawa
(County)

Located In: _____ Corner Code # _____

- | | | |
|------------------------------------|--------------------------|-------------------------|
| 1. Public Land Survey | T <u>5N</u> R <u>14W</u> | <u>H-13 (S 1/4, 34)</u> |
| | T _____ R _____ | <u>Zeeland Twp.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECORDED

96 DEC 17 AM 10:42

Elizabeth Coleman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John C. Bueche, in a field survey on November 4, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13 GLO	CP Co. show cor.
Lucuis Lyon, DS, 1831	1/2 way on straight line between
Set HMP	SW & SE corners
W Oak 20 N 61 E 31	Did not show they set cor.
Sugar 6 N 36 W 16	S 1/4 to SE 2649.89'
	S 1/4 to SW 2649.90'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found rerod on field division E-W on line between SE & SW corners of Sec. 34; field division N, West 150'±
Meas. W 2649.48' (CP 2649.90')
Meas. E 2650.10' (CP 2649.98')

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11-11-96

J.C.B.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
H-13 Replaced 30" rerod with Ottawa Co. Mon. (3/4" x 24" pin with cap)
Corner is on line between SW & SE 2649.48' W & 2650.10' E
Nail & Ottawa Co. Remon. Tag in S side 6" Oak N 80° E 115.09'
Field division North, West 150'±
On field division E & W
Nothing to wit. cor. to

\$ 9.00 CORNER
\$ 1.00 PHOTO



Signed by John C. Bueche
John C. Bueche, P.S.
Surveyor's Michigan License No. 13027

Date 11-7-96