

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

Ottawa County Remonumentation LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:49

D. J. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>14W</u>	<u>I-5 (SE, 10)</u>
	T _____ R _____	<u>Zeeland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-5 GLO, March, 1832 Calvin Britain, D.S. Set cor. Sugar 10 N 68 E 14 Beech 9 S 80 W 12	LCRC L1-P263 RR spk., Feb., 1972 Nail in face PP NW 93.65' Nail in face PP SW 50.40' Nail in face TP SE 45.30'	LCRC L1-P287 1 1/4" pipe on top RR spk., March, 1972 Nail in face TP N 50 E 41.15' Nail in face TP S 35 E 45.32'	LCRC L5-P171 Set CIM, Dec., 1984 10" Maple NE 98.15' "X" in culvt. ENE 49.67' C/L st. sign SE 39.19' PP SW 71.23'
---	--	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I-5 Found Ottawa Co. Mon. (2" Harrison) in Mon. Box
"X" in culvt. ENE 49.67'
PP SW 71.23'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Donald P. ...

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-5 Ottawa Co. Mon. (2" Harrison) in Mon. Box
Nail & Ottawa Co. Remon. Tag in S side PP S 75 W 71.31'
SE cor. conc. dr. @ bit. dr. N 10 W 134.90'
SE cor. brick hse. N 60 E 144.90'
"X" cut on conc. culvt. S 60 E 55.17'
C/L "X" of bit. N & S, W gravel E

Signed by John C. Bueche
Surveyor's Michigan License No. 13027

Date 12-12-94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983