

SUBJECT
REMONUMENTATION

1993

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 DEC 15 AM 9:31

For corners in
Ottawa
(County)

COMMISSION

Located In:

Corner Code #

- 1. Public Land Survey T 5N R 14W I-10 (E $\frac{1}{4}$, 27)
Zeeland Twp.
- 2. Property Controlling S ___ T ___ R ___
- in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
- Property in Sec. S ___ T ___ R ___
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Shirley Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on October 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-10 LCRC (L6, P7) Oct. 17, 1989
Set C.I.M.
PK in TP WSW 49.89'
PK in TP ESE 46.80'
NW cor. gar. @ face brick SE 109.78'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 Found O.C. Mon. (4" Harrison Mon.) in Mon. Box down 6'±, Mon.
Box flush with bit.
NW cor. gar. @ face brick SE 109.78'
PK in TP ESE 46.80'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 O.C. Mon. (4" Harrison Mon.) in Mon. Box
NW cor. gar. @ face brick S 77° E 109.68'
O.C. Remon. Tag & Nail in N side TP S 73° E 46.97'
SW cor. hse. #1184 @ face brick S 45° E 149.90'
C/L of 2" Tree N 40° E 93.44'
C/L N-S road is E 3'±
On field division W
Meas. by hand



Signed by John C. Bueche Date Nov. 29, 1993
Surveyor's Michigan License No. 13027