

**SURVEY &
REMONUMENTATION**

APR 24 1995

COMMISSION

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:49

Phyllis Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

| Ottawa (County) | Located In: | Corner Code # |
|---------------------------------------|-------------|----------------------------|
| 1. Public Land Survey | T 5N R 14W | J-5 (S $\frac{1}{4}$, 11) |
| | T R | Zeeland Twp. |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, John C. Bueche, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | |
|---|--|---|
| J-5 GLO, March, 1832 Calvin Britain, D.S. Set post on line Beech 9 N 40 E 16 Beech 10 S 59 W 30 | LCRC L3-P151 1" iron pipe St. sign SW 42.20' 18" Maple NNE 75.10' | LCRC L5-P171 Set CIM, Dec., 1984 PP NW 60.33' 4" Tree N 54.19' 4" Ash NE 41.15' St. sign SW 42.13' |
|---|--|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-5 Found Ottawa Co. Mon. (4" Harrison) in gravel rd.
PP NW 60.33'
St. sign SW 42.13'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Geordy P. Nedewald

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5 Ottawa Co. Mon. (4" Harrison) in gravel rd.
Nail & Ottawa Co. Remon. Tag in E side 8" Elm N 50 E 76.71'
Nail & Ottawa Co. Remon. Tag in E side 24" Maple N 05 E 75.19'
Nail & Ottawa Co. Remon. Tag in SW side PP N 55 W 60.46'
Nail & Ottawa Co. Remon. Tag in W side 10" Elm S 30 W 102.08'
Nail & Ottawa Co. Remon. Tag in W side PP S 25 E 48.62'
C/L gravel rd. E-W, N 6'±; C/L gravel rd. S, W 6'±

Signed by John C. Bueche Date 12-12-94
Surveyor's Michigan License No. 13027



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983