

**SURVEY &
REMONUMENTATION**

APR 05 1996

**Ottawa County Remonumentation
AND CORNER RECORDATION CERTIFICATE
COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>5N</u> R <u>14W</u>	J-9 (S $\frac{1}{4}$, 23)	<u>Zeeland Twp.</u>
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

RECORDED

95 NOV 29 PM 1:42

Phyllis Kallman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on November 13, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-9 GLO Calvin Britain, D.S. March, 1832 1/4 sec. post on true line 39.92' Beech 3 N 30 E 19 Lynn 10 S 20 W 18	LCRC L2-P671, Oct., 1974 Found splitting wedge 1' underground PK in PP S 35.52' PK in TP N 25.90' Sq. spk. in 24" Hickory SE 81.63'
--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9 Found splitting wedge 2.0'± below rd. grade
PK in PP S 35.52'
PK in TP N 25.90'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY

PEER APPROVED 11/20/95

Richard P. Redwood
R.P.R.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9 Replaced splitting wedge with 3/4" x 24" Pin with Ottawa Co. Cap
Set Nail & Ottawa Co. Remon. Tag in E side TP N 0 E 25.68'
Set Nail & Ottawa Co. Remon. Tag in NE side PP S 10 W 35.37'
Set Nail & Ottawa Co. Remon. Tag in SE side PP S 70 W 187.49'
Set Nail & Ottawa Co. Remon. Tag in SE side 36" Hickory N 75 E 123.55'
C/L gravel rd. South 4.0'±
On Tree row to North

Signed by John C. Bueche
John C. Bueche, P.S.
Surveyor's Michigan License No. 13027

Date Nov. 16, 1995

