

**SURVEY &  
REMONUMENTATION**

APR 05 1996

**COMMISSION Ottawa County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>14W</u>	<u>J-11 (S<math>\frac{1}{4}</math>, 26)</u> <u>Zeeland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**RECORDED**

95 NOV 29 PM 1:42

*Robert D. Hillman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John C. Bueche, in a field survey on November 13, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

J-11 GLO Calvin Britain, D.S. March, 1832 Set 1/4 post on true line 39.98' White Ash is post	LCRC L5-P84 Dec., 1988 Found RR spk. in Mon. Box Set cast iron mon. TP SE 41.17' PP NE 34.97' 18" Catalpa N 43.81' 20" Catalpa NW 31.59'
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-11 Found 4" cast iron mon. in Mon. Box in good condition  
PP NE 34.97'  
18" Catalpa N 43.81'  
20" Catalpa NW 31.59'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 346 OTTAWA COUNTY

PEER APPROVED 11/20/95

*Robert D. Hillman*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11 4" cast iron mon. in Mon. Box  
Ottawa Co. Remon. Tag & Nail in NW side guy pole S 45 W 46.68'  
NW cor. barn at fnd. S 25 E 133.63'  
Ottawa Co. Remon. Tag & Nail in SE side UP N 48 E 35.02'  
Ottawa Co. Remon. Tag & Nail in W side 26" Catalpa N 0 E 43.97'  
Ottawa Co. Remon. Tag & Nail in NE side 30" Catalpa N 30 W 31.30'  
On C/L gravel rd. South  
1'± North of C/L bit. rd. E-W

Signed by John C. Bueche  
John C. Bueche, P.S. 13027  
Surveyor's Michigan License No. \_\_\_\_\_

Date Nov. 16, 1995

