

**SURVEY &  
REMONUMENTATION**

APR 24 1995

COMMISSION

Ottawa County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

96 DEC 15 AM 11:49

*D. J. ...*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>14W</u>	<u>K-3 (SE, 2)</u>
	T _____ R _____	<u>Zeeland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on December 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

K-3 GLO, March, 1832 Calvin Britain, D.S. Set cor. Sugar 7 S 56 W 7 Beech 7 N 56 E 20	LCRC L2-P305 3/4" iron, Sept., 1973 PP SW 59.51' St. sign WSW 28.89' Cor. fe. post SE 38.66' Cor. fe. post NE 28.04'	LCRC L4-P35 T iron, March, 1980 PK on PP SW 69.59' PK on TP SE 64.5' PK on TP NE 64.6' C/L st. sign SW 34.02' Iron SSE 11.85'	LCRC L -P T iron, Feb., 1983 PK in SE PP SW 69.60' PK in NE TP SE 64.48' PK in NW PP NE 64.64' Iron SSE 11.90'
---	--	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-3 Found T iron down 1.5'±

As per above wit.

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94  
*Maday D. Nedewell*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3 Left T iron in place & set Ottawa Co. Mon. (3/4" x 24" Pin with Alum Cap) down 8"  
Nail & Ottawa Co. Remon. Tag in SE side PP S 35 W 69.33'  
Nail & Ottawa Co. Remon. Tag in W side PP N 40 E 65.04'  
Nail & Ottawa Co. Remon. Tag in E side PP N 05 W 298.71'  
NE cor. frame bldg. S 80 W 329.98'  
On C/L gravel rd. N-S  
Iron SSE 11.90'  
C/L gravel E, S 8'±

Signed by John C. Bueche  
Surveyor's Michigan License No. 13027

Date 12-12-94

