

**SURVEY &  
REMONUMENTATION**

APR 24 1995

**COMMISSION**

Ottawa County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:48

*Phyllis Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in  
Ottawa  
(County)

| Located In:             | Corner Code #              |
|-------------------------|----------------------------|
| T 5N R 14W              | K-4 (E $\frac{1}{2}$ , 11) |
| T _____ R _____         | Zeeland Twp.               |
| T _____ R _____         | _____                      |
| T _____ R _____         | _____                      |
| S _____ T _____ R _____ | _____                      |
| S _____ T _____ R _____ | _____                      |
| S _____ T _____ R _____ | _____                      |
| S _____ T _____ R _____ | _____                      |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 | ▲ | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

I, John C. Bueche, in a field survey on December 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

|                            |                         |                                  |                                   |
|----------------------------|-------------------------|----------------------------------|-----------------------------------|
| K-4 GLO, March, 1832       | LCRC L3-P150            | LCRC L4-P35                      | LCRC L5-P202                      |
| Calvin Britain, D.S.       | T iron, Jan., 1977      | Large T iron, March, 1980        | T fe. post, Feb., 1985            |
| Set 1/2 mile post Sugar 30 | 18" Cherry SE 39.26'    | MSHD tag 20" W. Cherry SE 39.05' | Set Nail NW 30" Maple SW 62.23'   |
| N 65 W 5                   | 22" Maple stump W 43.0' | Nail & tag N 26" Maple SW 62.3'  | Set Nail W 18" W. Cherr SE 38.96' |
| Beech 9                    | 28" Maple SW 62.5'      | Face TP SSW 71.46'               | Face TP SSW 71.35'                |
| S 49 E 16                  |                         |                                  |                                   |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-4 Found 1/2" rerod & T fe. post in gravel rd.

As per above wit.

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94  
*Woodrow D. Hedderwell*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 Removed rerod, left T fe. post, set Ottawa Co. Mon. (3/4" x 24" Pin with Alum. Cap) in gravel rd.  
Nail & Ottawa Co. Remon. Tag in S side 16" Oak S 85 E 75.81'  
Nail & Ottawa Co. Remon. Tag in W side 28" Maple S 40 W 62.30'  
Nail & Ottawa Co. Remon. Tag in SW side 22" Ash S 40 E 55.60'  
Nail & Ottawa Co. Remon. Tag in N side 12" Maple S 25 E 93.63'  
On N edge of woods E, on tree row W, C/L gravel rd. N-S, E 3'±

Signed by John C. Bueche  
Surveyor's Michigan License No. 13027

Date 12-12-94

