

**Ottawa County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ottawa

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>5N</u> R <u>14W</u>	<u>K-5 (SE, 11)</u>
	T _____ R _____	<u>Zeeland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**RECORDED**

96 DEC 17 AM 10:42

*R. J. Callman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche, in a field survey on October 21, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

K-5 GLO	CP Co.	Allegan Co. Surveyor
Calvin Britain,	Fnd. iron	SW to S 2643.93'
1832	St. sign SE 59.10'	Ottawa Co. Records
Set cor. to	GP SE 45.50'	SW to S 1/4 2644'
Secs. 11-14	TP NW 44.65'	SW to W 2632'
Beech 4 N 74 E 5	in C/L X rd. N-S, E-W	
Beech 5 S 83 W 20	SW cor. to S 1/4	1894
	2644.04'	SW to S 1/4 2643.92'
	SW cor. to W 1/4	SW to W 2631.57'
	2651.40'	

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K-5 Found 1" x 30" solid pin in gravel road  
Wit. all gone  
Meas. E 1322.08' (CP Co. 1322.04', fnd. T iron)  
Meas. S 2641.34' (Ottawa Co. Mon.)

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY


PEER APPROVED 11-11-96

*J.C.B.*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-5 Replaced 1" x 30" solid pin with Ottawa Co. Mon. (3/4" x 24" pin with cap) in gravel road  
X cut in North end concrete culvert N 73° W 61.25'  
X cut in South end concrete culvert S 73° W 60.45'  
X cut in West end concrete culvert S 10° W 80.39'  
X cut in East end concrete culvert S 16° E 81.57'  
X cut in South end concrete culvert S 78° E 70.16'  
On C/L gravel roads S & E

\$ 9.00 CORNER  
\$ 1.00 PHOTO



Signed by John C. Bueche  
John C. Bueche, P.S. 13027

Date 11-7-96

Surveyor's Michigan License No. \_\_\_\_\_