

SURVEY & REMONUMENTATION

APR 05 1996

COMMISSION

**Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED
95 DEC 12 PM 4:51

Register of Deeds
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in
Ottawa
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>14W</u>	K-6 (E ₁ , 14) Zeeland Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on November 30, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-6 GLO	LCRC L1-P459
Calvin Britain	June, 1972 Iron
March, 1832	Nail in side 24" Maple SW 41.35'
Set 1/2 mile post	Nail in side 16" Maple W 22.60'
Beech 30 S 35 W 6	Nail in side PP NE 86.57'
Beech 10 S 89 E 24	Nail in side 28" Maple NW 38.10'
	NE cor. block barn NW 119.32'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6 Found T iron in gravel rd., down 0.2'±
Check above wit. ±
C/L gravel rd. N-S, E 3'±
C/L gravel rd. E, N 6'±

And is accepted as a careful and faithful perpetuation of the position of the original corner.

PA. 845 OTTAWA COUNTY
PEER APPROVED 12/11/95

Madison D. Hedwell
L.D.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 Replaced T iron with 3/4" x 24" Pin with Ottawa Co. Cap
Set Nail & Ottawa Co. Remon. Tag in SE side PP N 60 E 86.54'
Set Nail & Ottawa Co. Remon. Tag in N side 24" Maple N 80 W 22.52'
Set Nail & Ottawa Co. Remon. Tag in SE side 36" Maple S 40 W 41.27'
Set Nail & Ottawa Co. Remon. Tag in NE side 40" Maple N 30 W 37.95'
C/L gravel rd. N-S, E 3'±
C/L gravel rd. E, N 6'±

Signed by John C. Bueche
John C. Bueche, P.S. 13027
Surveyor's Michigan License No. _____

Date 12-6-95



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1993