

**SURVEY &
REMONUMENTATION**

APR 25 1995

COMMISSION

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
94 DEC -8 PM 12:38

or corners in

Ottawa

(County)

Located In:

Corner Code #

Public Land Survey

T 5N R 14W

K-7 (NW, 24)

T _____ R _____

Zeeland Twp.

T _____ R _____

T _____ R _____

Property Controlling
in Section

S _____ T _____ R _____

Miscellaneous

S _____ T _____ R _____

Property in Sec.

S _____ T _____ R _____

Richard Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____

Private Claims _____

John C. Bueche in a field survey on October 12, 1994

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Description of original monument and accessories and/or subsequent restoration:

K-7 GLO March, 1832	LCRC L4-P152 Boat spk., Feb., 1981	LCRC L5-P164 CIM, Dec., 1984
Calvin Britain, D.S.	St. sign SE 43.22' PP SE 57.07'	MHSD Tag PP SE 57.23' MHSD Tag PP SW 58.46'
Set post	PP SW 58.25'	Stop sign NW 58.76'
Sugar 10 N 89 W 23	NE hse. cor. SW 141.42'	
Beech 20 S 65 E 20		

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7 Found Ottawa Co. Mon. (2" Harrison) in Mon. Box in bit. rd.
As per above wit. As per above wit.

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/21/94

Richard P. Newell

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7 Ottawa Co. Mon. (2" Harrison) in Mon. Box	
Nail & MSHD Tag in SW side PP	S 30 E 57.39'
Nail & MSHD Tag in SE side PP	S 40 W 58.43'
Nail & Ottawa Co. Remon. Tag in W side PP	N 15 E 165.59'
Nail & Ottawa Co. Remon. Tag in top of wood fence post	N 50 E 68.19'
NE cor. hse. (brick)	S 42 W 141.46'
C/L bit. E-W,	N 1'+
On C/L bit. S, on C/L gravel N	

signed by John C. Bueche
John C. Bueche
Surveyor's Michigan License No. 13027

Date 11-18-94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983