

**Ottawa County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>14W</u>	<u>K-13 (SE, 35)</u>
	T _____ R _____	<u>Zeeland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**RECORDED**  
96 DEC 17 AM 10:42  
*Richard R. Hartman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

**Register of Deeds Stamp & File Number**

I, John C. Bueche, in a field survey on November 4, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

K-13 GLO	LCRC L3, P70	CP Co., no date
Set post corner	April 6, 1976 T iron	Fnd. stake, set iron
Secs. 35 & 36	C/L gravel rd. North	4" Maple SSW 77.25'
Elm 8 N 43 W 11	Rd. sign N 50° E 17.30'	PP SW 109.52'
Elm 28 N 35 E 33	TP N 35° E 35.05'	TP NE 35.01'
Lucuis Lyon	PP S 55° W 64.38'	C/L in end pipe NE 23.63'
Nov., 1831		In C/L X rds.; E to S 1/4 36
		2643.82'
		N to E 1/4 35 2641.68'
		W to S 1/4 35 2651.58'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K-13 Found reroed in Mon. box  
PP S 55° W 63.5'±

C/L bit. N-S, West 3'±  
On C/L 2 track East Meas. N to E 1/4 35 2642.83'  
C/L 2 track West, North 4'± Meas. W to S 1/4 35 2646.68' set cor.  
(old Co. Records 2644.50')  
Meas. E to S 1/4 36 2644.18'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

**P.A. 345 OTTAWA COUNTY**  
**PEER APPROVED** 11-11-96

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-13 Replaced reroed with Ottawa Co. Mon. (3/4" x 24" pin with cap) in Mon. box

Nail & Ottawa Co. Remon. Tag in S side PP S 50° W 108.64'  
Nail & Ottawa Co. Remon. Tag in N Side PP S 60° W 63.40'  
Nail & Ottawa Co. Remon. Tag in S side gate post S 70° E 41.08'  
X cut in top of N end CMP S 55° W 34.01'  
X cut in top of N end CMP N 60° E 31.26'  
On C/L bit. N-S, West 3'±, on C/L 2 track East

\$ 9.00 CORNER  
\$ 1.00 PHOTO

Signed by John C. Bueche  
John C. Bueche, P.S.  
Surveyor's Michigan License No. 13027

Date 11-7-96

