

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:38

D. J. ...
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 5N R 14W	L-7 (N $\frac{1}{4}$, 24)
	T _____ R _____	Zeeland Twp.
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
 2. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

John C. Bueche, in a field survey on October 12, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

L-7 GLO March, 1832	LCRC L1-P459	LCRC L5-P164
Calvin Britain, D.S.	RR spk., June, 1972	CIM, Dec., 1984
Set post Pine 18 N 21 W 15	Nail in side PP SW 48.60'	PP S 48.60'
Elm 10 S 31 E 8	Nail in side 18" Ash NNW 33.0'	18" Ash NW 52.80'
	Nail in side 30" Maple NNW 57.80'	32" Maple NNW 57.85'
	Nail in side dbl. 18" Maple ENE 100.23'	Stop sign SE 51.16'

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7 Found Ottawa Co. Mon. (2" Harrison) in Mon. Box
 Nail in side PP SW 48.60' As per above wit.
 Nail in 30" Maple NNW 57.80'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 11/21/94


Handwritten signature

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7 Ottawa Co. Mon. (2" Harrison) in Mon. Box	
Nail in Ottawa Co. Remon. Tag in E side PP	S 40 W 48.67'
Nail in Ottawa Co. Remon. Tag in W side 6" Elm	N 00 E 49.25'
Nail in Ottawa Co. Remon. Tag in top of 6"x8" wood fe. post	S 30 E 75.42'
Nail in Ottawa Co. Remon. Tag in top of 6"x8" wood fe. post	S 50 E 76.14'
Nail in Ottawa Co. Remon. Tag in E side 16" Box Elder	N 20 W 52.91'
On C/L bit. E-W, on C/L gravel S	
On tree row N	

Signed by John C. Bueche
 John C. Bueche
 Surveyor's Michigan License No. 13027

Date 11-18-94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983