

**Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Ottawa
(County)

Located In:	Corner Code #:
T <u>5N</u> R <u>14W</u>	<u>L-13 (S 1/4, 36)</u>
T _____ R _____	<u>Zeeland Twp.</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

RECORDED

96 DEC 17 AM 10:41

Richard R. Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche, in a field survey on November 4, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13 GLO	CP Co.
Lucius Lyon, DS, 1831	Set iron
Set HMP	12" Oak NNE 11.97'
W. Oak 7 N 22 W 18	20" Maple ESE 30.5'
Maple 5 N 62 E 60	10" Oak S 73.35'
	10" Maple SW 38.75'
	S 1/4 to SE 2637.82'
	S 1/4 to SW 2643.82'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 Found T iron
12" Oak NNE 11.97'+
Meas. 2644.18' from SW cor. (2643.82' CP Co., Nederveld 2644.31')
Old fence South
On N edge of clearing

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11-11-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 Replace T iron with Ottawa Co. Mon. (3/4" x 24" pin with cap)
Nail & Ottawa Co. Remon. Tag in S side 6" Ash N 80° E 10.51'
Nail & Ottawa Co. Remon. Tag in E side 12" Ash N 30° E 36.58'
Nail & Ottawa Co. Remon. Tag in E side 8" Ash N 30° W 45.95'
Nail & Ottawa Co. Remon. Tag in N side 12" Oak N 65° W 37.92'
Old E-W fence North 12'±; C/L Power Line E-W, South 37'±
On North edge of clearing, on old fence South

\$ 9.00 CORNER
\$ 1.00 PHOTO



Signed by John C. Bueche
John C. Bueche, P.S.
Surveyor's Michigan License No. 13027

Date 11-7-96

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1993