

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

Ottawa County Remonumentation LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:48

For corners in

Richard D. Hallman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 5N R 14W	M-4 (E $\frac{1}{2}$, 12) Zeeland Twp.
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<i>Tag #1 pm</i>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-4 GLO, March, 1832	LCRC L4-P341
Calvin Britain, D.S.	Set cast iron mon.
Set HMP	6" Apple ESE 73.81'
Beech 9 N 28 W 8	R/W marker NE 59.89'
Beech 6 S 20 W 23	St. sign SE 86.46'
	Jamestown cor. S 45.81'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4 Found Ottawa Co. Mon. (4" Harrison with top broke off) down 8" in gravel rd.

6" Apple	ESE 73.81'
R/W marker	NE 59.89'
Jamestown cor.	S 45.81'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Richard D. Hedewald

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 Ottawa Co. Mon. (4" Harrison with top broke off)
Nail & Ottawa County Remon. Tag in S side 8" Apple S 80 E 73.83'
Nail & Ottawa County Remon. Tag in N side 18" Oak N 65 E 65.82'
Nail & Ottawa County Remon. Tag in W side PP S 25 W 75.03'
Top C/L conc. ROW marker N 35 E 60.05'
Field division W, N 12'±
C/L gravel N-S, E 2'±; C/L gravel E, S 46'±
Jamestown cor. iron S 45.81'

Signed by John C. Bueche
Surveyor's Michigan License No. 13027

Date 12-12-94

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 28, 197
REVISOR MAY 14, 197
REVISOR JAN., 198

