

**Ottawa County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>14W</u>	<u>M-5 (SE, 12)</u>
	T _____ R _____	<u>Zeeland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<u>Sept. #1 pin</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**RECORDED**

95 DEC 17 AM 10:41

*Richard S. Hallman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John C. Bueche, in a field survey on October 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-5 GLO	LCRC L4, P341
Set P. cor. Secs. 12 & 13	Sept. 24, 1982 fnd. T iron, set CIM
Sugar 7 N 25 W 18	TP NW 40.18'
Lynn 7 S 35 W 38	TP ESE 42.13'
Lucius Lyon	GP SSE 105.31'
Nov., 1831	PP SW 90.54'
	Jamestown cor. S 44.21'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 Found 1/2" rerod bent  
Ottawa Cast Iron Mon. S 44.21', down 1.5'  
PP SE 86'±

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 11-11-96

*J.C.B.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 Replaced 1/2" rerod with Ottawa Co. Mon. (3/4" x 24" pin with cap)  
NE cor. hse. fnd. N 30° W 211.74'  
SW cor. conc. porch N 43° W 192.56'  
Nail & Ottawa Co. Remon. Tag in E side PP S 16° W 85.99'  
Nail & Ottawa Co. Remon. Tag in E side PP N 7° W 189.93'  
C/L top E end CMP N 29° E 42.80'  
On C/L gravel road N-S  
On C/L gravel road W, extend East; on C/L bit. road E, extended West

\$ 9.00 CORNER  
\$ 1.00 PHOTO

Signed by John C. Bueche  
John C. Bueche, P.S. 13027  
Surveyor's Michigan License No. \_\_\_\_\_

Date 11-7-96

