

SURVEY & REMONUMENTATION

FEB 27 1998

**Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ottawa</u> SECTION	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>5N</u> R <u>14W</u>	<u>M-5</u>
	T _____ R _____	<u>ZEELAND TWP</u>
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	<u>Seg #2 pm</u>
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

RECORDED

97 DEC -8 AM 11:31

[Signature]
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Rodney D. Unema, in a field survey on Nov. 26, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-5 Remon Liber 3, Page 293 (Dec. 17, 1996)
Replaced 1/2" rerod with O.C. Mon. (3/4" X 24" pin with cap)
NE cor. hse. fnd. N30°W 211.74'
SW cor. conc. porch N43°W 192.56'
Nail & O.C. Remon. Tag in E side PP S16°W 85.99'
Nail & O.C. Remon. Tag in E side PP N7°W 189.93'
On ϕ gravel road N-S
On ϕ gravel road W, extend East; on ϕ bit. road E, extended West

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5
Found O.C. Mon. as described in Remon Liber 3, Page 293
NE cor. hse fndn. N30°W 211.76'
SW cor. conc. porch N43°W 192.52'
Nail & O.C. Tag in E side PP S16°W 86.02'

Rewitnessed corner and after road construction held witnesses to set standard Ottawa County Cap on 24" X 3/4" Steel Bar in Mon. Box

P.A. 345 OTTAWA COUNTY

PEER APPROVED 12-1-97

[Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5
Standard Ottawa County Cap on 24" X 3/4" Steel Bar in Mon. Box
NE cor. hse. fndn. N30°W 211.70'
SW cor. conc. porch N43°W 192.52'
Nail & Tag in E side PP S16°W 86.02'
Nail & Tag in E side PP N10°W 103.07'
Nail & Tag in E end 24" CMP N40°E 49.11'
Nail & Tag in E end 18" CMP S21°E 78.52'
O.C. Mon. (A-5, Jamestown Twp.) S4°W 44.24'
On ϕ N-S BT road
On ϕ BT road to West extended



Signed by Rodney D. Unema
Surveyor's Michigan License No. 33987

Date Dec. 1, 1997