

RECORDED

Ottawa County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

97 JUL 24 PM 2:23

*Phyllis Kullman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in  
Ottawa

(County)

Located In:

Corner Code #

- |                                       |                          |                     |
|---------------------------------------|--------------------------|---------------------|
| 1. Public Land Survey                 | T <u>5N</u> R <u>14W</u> | <u>M-7 (NE, 24)</u> |
|                                       | T _____ R _____          | <u>Zeeland Twp.</u> |
|                                       | T _____ R _____          | _____               |
|                                       | T _____ R _____          | _____               |
| 2. Property Controlling in Section    | S _____ T _____ R _____  | _____               |
|                                       | S _____ T _____ R _____  | _____               |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____  | _____               |
|                                       | S _____ T _____ R _____  | _____               |
| 4. Lot No. _____, Recorded Plat _____ |                          |                     |
| 5. Private Claims _____               |                          |                     |

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on April 1, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-7	LCRC L3, P37	LCRC L3, P114
GLO Nov., 1831	1" iron in Mon.	1/2" iron, Oct., 1976
Lucius Lyon, DS	Box, Mar., 1976	St. sign SSE 79.65'
Set HMP	PP SW 70.53'	On C/L bit. West
Sugar 10 N 20 W 38	PP NW 59.59'	C/L gravel rd. W 4'±
Elm 13 S 50 W 23	PP SE 51.02'	1/2" iron (NW Sec. 19, 5-13), South 62.0

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7 Found Ottawa Co. Mon. in Mon. Box (down 0.8', 2" Harrison)  
Mon. Box South 62.0'  
Meas. N 2648.48'  
Meas. S 2653.01'  
Meas. W 2652.19'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Fence South 1324'± (Comp. 1326.08')  
Tree line North 1991'± (Comp. 1989.14')  
Joiner, MVK, HEI had no meas. West


PA. 345 OTTAWA COUNTY

PEER APPROVED 6-16-97

*S.D.N.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

M-7 Ottawa Co. Mon. in Mon. Box (down 0.8', 2" Harrison)  
Nail & Ottawa Co. Remon. Tag in N side PP S 84° E 108.40'  
Nail & Ottawa Co. Remon. Tag in E side PP S 12° W 213.41'  
Nail & Ottawa Co. Remon. Tag in N side PP S 70° W 168.23'  
NW cor. hse. fnd. S 40° W 281.74'  
Mon. Box South 62.34'  
On C/L Mon. Box bit. W extended E, on C/L South gravel rd. South,  
C/L gravel rd. N is West 7'±



Signed by John C. Bueche

John C. Bueche, P.S.

Date 4-16-97

Surveyor's Michigan License No. 13027

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 197  
REVISED MAY 14, 197  
REVISED JAN., 198