

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

DEC -8 PM 12:38

Reginald K. Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

or corners in

Ottawa <small>(County)</small>	Located In:	Corner Code #	
Public Land Survey	T <u>5N</u> R <u>14W</u>	M-9 (SE, 24)	Zeeland Twp.
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
Property Controlling in Section	S _____ T _____ R _____	_____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

John C. Bueche, in a field survey on October 10, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

M-9 GLO Nov., 1831	LCRC L5-P347, Dec., 1988
Sylvester Sibley, D.S.	CIM
Set post	CIM SW cor. 19, 5-13 S 20.43'
Beech 10 S 22 W 9	22" Catalpa SW 44.35'
Sugar 8 N 51 W 33	1/2" rod NW 35.0'
	18" Maple NE 47.93'
	TP SE 80.58'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9 Found Ottawa Co. Mon. (Harrison Mon.)
As per above wit.

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/21/94

Gregory P. Nedwell



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 Ottawa Co. Mon. (Harrison Mon.)	
Nail & Ottawa Co. Remon. Tag in SE side 36" Catalpa	S 50 W 44.05'
Nail & Ottawa Co. Remon. Tag in N side Pole	S 75 W 72.31'
Nail & Ottawa Co. Remon. Tag in W side 26" Elm	N 50 E 48.24'
Nail & Ottawa Co. Remon. Tag in W side Pole	S 20 E 80.70'
Ottawa Co. Mon. SW cor. 19, 5-13	S 20.43'
C/L gravel rd. N-S	E 4'±
C/L gravel rd. W	N 2.5'±
C/L gravel rd. E	S 29'±

Signed by John C. Bueche Date 11-18-94
Surveyor's Michigan License No. 13027