

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:38

For corners in

Ottawa

(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>5N</u>	R	<u>14W</u>	<u>M-11 (SE, 25)</u>
	T		R		<u>Zeeland Twp.</u>
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Reginald C. Holliman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

John C. Bueche, in a field survey on September 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11 GLO Nov., 1831	LCRC L1-P185 Dec., 1971	LCRC L3-P78 April, 1976	LCRC L5-P83 Cast iron mon.
Sylvester Sibley, D.S.	Iron in Mon. Box CP pole	Mon. Box 15" Hickory	PP SW 82.00'
Set post	S 40 W 81.90'	NNE 77.30'	Fe. post SE 35.79'
Sugar 8	CP pole	PP NW 65.0'	PP NE 48.18'
S 28 W 33	N 32 W 64.55'	PP NE 48.2'	TP NW 65.20'
Hickory 6	20" Hickory		
N 58 W 28	N 25 E 76.05'		

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 Found Ottawa Co. (Harrison Mon.) in Mon. Box (broken top 2" gone, no cover on box)	20" Hickory	PP NE 48.2'	PP NE 48.18'
	N 25 E 76.05'		
	C/L pav't. N 2'±		

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/21/94

C. Description of monument for corner and accessories established to perpetuate location of the position of the corner:

M-11 Ottawa Co. Mon. (Harrison Mon.) in Mon. Box (Cap broken off)	
Nail & Ottawa Co. Remon. Tag in SE side	PP S 55 W 40.23'
Nail & Ottawa Co. Remon. Tag in E side	PP S 20 W 77.76'
Nail & Ottawa Co. Remon. Tag in SE side	UP N 55 E 48.32'
Nail & Ottawa Co. Remon. Tag in S side	PP N 75 E 184.34'
Nail & Ottawa Co. Remon. Tag in E side	PP N 05 W 120.45'
On C/L grave N-S	
C/L bit. E-W	N 2'±
No evidence of closing corner	NE 31, 5-13

Signed by John C. Bueche
John C. Bueche
Surveyor's Michigan License No. 13027

Date 11-18-94

