

SURVEY & REMONUMENTATION

APR 05 1996

COMMISSION

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

95 DEC 12 PM 4:51

Polypolis Robinson
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in
Ottawa

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|---|
| 1. Public Land Survey | T <u>5N</u> R <u>14W</u> | <u>M-12 (E$\frac{1}{2}$, 36)</u> |
| | T _____ R _____ | <u>Zeeland Twp.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John C. Bueche, in a field survey on November 30, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-12 GLO Lucius Lyon, D.S. Nov., 1831 Set HMP Beech 24 N 15 W 26 Beech 12 S 15 W 44	LCRC L3-P31 Jan., 1976 Found stone, iron, plowpoint Set CIM St. sign ESE 39.73' PP SE 68.97' NE cor. conc. fnd. corn crib WSW 37.70'	LCRC L3-P70 April, 1976 Found stone, crockery & plowpoint St. sign S 50 E 39.75' PP S 40 E 69.17' NE cor. corn crib S 80 W 37.85'
--	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12 Found Cast Iron Mon. down 0.8' in gravel rd.
 PP S 40 E 69.17'
 On C/L gravel rd. East, on field division West
 C/L gravel rd. N-S, East 3'±

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 12/11/95


Handwritten signature: Audrey D. Hedewell
MON

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 Cast Iron Mon.
 Existing Nail & Tag #14091 in NE side PP S 40 E 69.08'
 Set Nail & Ottawa Co. Remon. Tag in E side PP N 05 W 213.13'
 Set Nail & Ottawa Co. Remon. Tag in NW side PP S 20 W 94.56'
 SE cor. conc. fnd. to shed N 70 W 128.36'
 On C/L gravel rd. East, on field division West
 C/L gravel rd. N-S, East 3'±

Signed by John C. Bueche
 John C. Bueche, P.S. 13027
 Surveyor's Michigan License No. _____

Date 12-6-95



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983