

FEB 24 2000

RECORDED

OTTAWA COUNTY REMONUMENTATION

99 DEC -2 PM 1:12

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Randy Scholtz*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

OTTAWA

(County)

Located In:

Corner Code #

1. Public Land Survey

T 5N R 14W

M-7 NE corner

T R

Section 24, Zeeland

T R

Twp

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

*Sec. 2*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Randal J. Vugteveen, in a field survey on September 27, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-7 Peer Approved Corner (Liber 3, Page 481 Bueche 4/16/97)  
O.C. Mon. in Mon. Box (down 0.8', 2" Harrison)  
Nail & Remon Tag N side P. Pole S84°E 108.40'  
Nail & Remon Tag E side P. Pole S12°W 213.41'  
Nail & Remon Tag in N side P. Pole S70°W 168.23'  
NW corner house foundation S40°W 281.74'  
Mon. Box South 62.34'  
On centerline South gravel road South  
Centerline gravel road N is West 7'+/-

RECORDED  
11/15/99  
*YD*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7 Found 2 1/2" Cast Iron Monument (1.5' below surface)

Fnd Nail & Remon Tag N side P. Pole S83°E 108.38'  
Fnd Nail & Remon Tag N side P. Pole S74°W 168.21'  
Fnd Nail & Remon Tag N side P. Pole S13°W 213.40'  
NW corner house fndn S41°W 281.72'  
Cast Iron Monument in Mon. Box S0°E 62.19'

Accepted 2 1/2" Cast Iron Monument as a careful & faithful perpetuation of the position of the original corner.

Set 3/4" X 1.2' Long Solid Bar with Remon Cap on Top of 2 1/2" Cast Iron Monument

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 3/4" X 1.2' long solid bar ~~with~~ <sup>with</sup> remon cap on top of 2 1/2" Monument

Found Nail & Remon Tag in N side P. Pole S83°E 108.38'  
Found Nail & Remon Tag in N side P. Pole S74°W 168.21'  
Found Nail & Remon Tag in N side P. Pole S13°W 213.40'  
NW Corner house Fndn S41°W 281.72'  
Set Nail & Remon Tag in West side light pole S36°W 71.13'  
Cast Iron Monument in Mon. Box (Jamestown A-7 corner) S0°E 62.19'  
On Centerline North and South Gravel Road (to be paved this week)  
Centerline Byron Road South 31'



\$9.00 CORNER  
Receipt #64945

Signed by *Randal J. Vugteveen*  
Surveyor's Michigan License No. 28429

Date OCTOBER 27, 1999