

**SURVEY & REMONUMENTATION**

DEC 01 1998

**SECTION**

Ottawa County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
 98 MAY 22 PM 4: 06

*Dany [Signature]*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code =#
1. Public Land Survey	T <u>5N</u> R <u>15W</u>	<u>A-4 (W<math>\frac{1}{2}</math>, 7)</u>
	T _____ R _____	<u>Holland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on March 30, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-4 GLO Did not set corner	LCRC 1-805, Dec., 1972 Fnd. iron pipe "T" iron Park Twp. South 29.13' Iron East 33.00' 16" Oak ESE 102.03' C/L Wolverine Pipeline Marker NE 33.96'	LCRC 3-393, Oct., 1979 Fnd. iron pipe Same as LCRC 1-805
-------------------------------	---	--

**OVER**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-4 Found N/A capped rerod on C/L bit. road N-S & on field division East  
 On Township Line between M-4 (E 1/4 12) & M-3 (SE 1) 5-16  
 As per LCRC 1-805, 5-15  
 Wit. from Exxel 1984  
 Wit. from Nederveld 1997

This position not established by original government surveyors.  
 This monument is accepted as the best available evidence of the position of the corner.

*[Signature]* 4/20/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4 Replaced capped iron with 3/4" x 24" pin & Ottawa Co. Cap & Mon. Box  
 Nail & Ottawa Co. Remon. Tag in E side UP S 10° W 159.46'  
 Nail & Ottawa Co. Remon. Tag in N side 24" Maple S 70° E 102.94'  
 Nail & Ottawa Co. Remon. Tag in E side UP N 10° W 161.93'  
 Top C/L hyd. S 60° E 43.01'  
 NE cor. fnd. hse. S 60° W 193.72'  
 On C/L bit. N-S; on field division East  
 Capped N/A rerod M-4 (E 1/4 12, 5-16) South 29.15'



Signed by John C. Bueche  
 John C. Bueche P.S. 13027  
 Surveyor's Michigan License No. \_\_\_\_\_

Date 4-1-98

**SURVEY &  
REMONUMENTATION**

DEC 01 1998

A-4

PART A - continued

SECTION

LCRC 5-15, March, 1983  
 NW 33.90' Wolverine Pipeline Marker  
 S 29.13' Park Twp. "T" iron  
 SE 37.62' to C/L Wolverine Pipeline Marker  
 ESE 103.93' Nail & Cap S side 20" Oak  
 E 33.0' to RLS iron

Exxel, June, 1984  
 4" CI Mon.  
 Nail in side 16" Oak ESE 102.72'  
 Nail in side PP NNW 161.64'  
 C/L pipeline marker NW 34.30'  
 Iron E 33.08'  
 E ¼ Sec. 12 S 29.13'

Nederveld, Sept., 1997  
 Nail in E side PP N 10° W 161.90'  
 Nail in N side 22" Oak S 70° E 102.94'  
 Nail in W side 6" Ash S 30° E 111.69'  
 Nail in E side PP S 10° W 159.44'  
 N/A capped @ R/W S 90° E 32.99'

